

Detailed Estimate

SoR Period: 08/05/2025 - 08/04/2026 Created By: BASANT DHRUV

AS No:3304008004/2025-2026/59644/AS TS No:3304008004/2025-2026/59644/TS

Construction of Cattle Shelter for Banwali/Maniram GP-Marri Marri

3304008004/IF/1111986096

BLOCK: Mohla, GRAMA PANCHAYAT : Marri

Heading / Description: 1 - CATTLE SHED								
1	79.01.01 -- Site clearance, cutting grass, raking into heaps and removing off the premises							
SI No	Description	No	L	B	D	CF	Quantity	Remark
SITE CLEARANCE								
1	site clearance	1	7.700	3.900		1.0	30.0300	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0108	261.0	2.82	0.3243	84.65	
Total Quantity					30.0300 sqm			
Total Deducted Quantity					0.0000 sqm			
Net Total Quantity					30.03 sqm			
Say 30.0300 sqm @ (₹) 2.931552 / sqm					88.03			
Unskilled wage					84.65			
Unskilled Person-days					0.324324			
2	79.03.07b -- Earth work in excavation in trenches for foundations and for pipes, cables etc. not exceeding 1.5m and for shafts, cesspits and the like not exceeding 10sqm on plan including dressing of sides and ramming of bottom upto 1.5m including getting (b) Dense or hard soil							
SI No	Description	No	L	B	D	CF	Quantity	Remark
Earthwork								
1	columns	6	0.900	0.900	0.900	1.0	4.3740	-
2	urinal	1	0.700	0.700	0.700	1.0	0.3430	-
LIST								

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0115	Coolie	Day	0.6670	261.0	174.09	3.1462	821.17
Total Quantity					4.7170 cum		
Total Deducted Quantity					0.0000 cum		
Net Total Quantity					4.72 cum		
Say 4.7170 cum @ (₹) 181.05048 / cum					854.02		
Unskilled wage					821.17		
Unskilled Person-days					3.1462389999999996		

3	79.04.300 -- False work for R.C.C. and P.C.C. work in plinth and foundation False work for R.C.C. and P.C.C. work in plinth and foundation						
---	--	--	--	--	--	--	--

SI No	Description	No	L	B	D	CF	Quantity	Remark
Falsework								
1	long wall o/o	2	7.700		0.200	1.0	3.0800	-
2	inner	2	7.300		0.200	1.0	2.9200	-
3	short wall o/o	2	3.900		0.200	1.0	1.5600	-
4	inner	2	3.500		0.200	1.0	1.4000	-
5	columns	24	0.700		0.200	1.0	3.3600	6*4 sides=24
6	Columns Above trap section to GL	24	0.200		0.350	1.0	1.6800	6*4 sides=25
7	column above GL	12	0.200		1.200	1.0	2.8800	3*4 sides=12 (E sidecolumns)
8	column above GL	12	0.200		0.450	1.0	1.0800	3*4 sides=12 (fr columns

LIST							
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0112	Carpenter 2nd class	Day	0.1488	435.0	64.73	2.6726	1162.59
0115	Coolie	Day	0.1488	261.0	38.84	2.6726	697.55
1197	Second class kail wood in scantling	10 cud m	0.0321	5200.43	167.16	0.5773	3002.13
Total Quantity					17.9600 sqm		
Total Deducted Quantity					0.0000 sqm		
Net Total Quantity					17.96 sqm		
Say 17.9600 sqm @ (₹) 281.557198 / sqm					5056.77		
Unskilled wage					697.55		

Unskilled Person-days						2.6726190672796934		
4	79.09.04b -- Providing and placing in position tested steel for R.C.C. work including cutting, bending, binding et drawings and placing in position complete up to floor two level including cost of binding wire and all wastage etc complete. (b) Cold twisted / Hot rolled deformed / Thermo mechanically treated steel bars							
SI No	Description	No	L	B	D	CF	Quantity	Remark
iron work								
1	columns mate 10 mm dia bar	48	0.650			0.62	19.2500	6 columns x4*2
2	back side columns	12	1.900			0.89	20.2460	1.3+0.35+0.25
3	front columns	12	1.250			0.89	13.3200	0.45+0.20+0.35
4	PLB LONG WALLBOTTOM BAR	4	7.650			0.89	27.1730	-
5	PLB LONG WALLTOP BAR	4	7.650			0.62	18.8800	-
6	PLB SHORT WALLBOTTOM BAR	4	3.850			0.89	13.6750	-
7	PLB SHORT WALLTOP BAR	4	3.850			0.62	9.5020	-
8	Stirrups columes	71	0.910			0.4	25.5210	-
9	stirrups PLB	155	0.910			0.4	55.7150	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
1005	Twisted steel/deformed bars	quintal	0.0105	6577.0	69.06	2.1345	14038.35	
7335	Binding wire	kilogram	0.0100	75.84	0.76	2.0328	154.17	
0115	Coolie	Day	0.0100	261.0	2.61	2.0328	530.57	
0102	Blacksmith 1st class	Day	0.0100	465.0	4.65	2.0328	945.26	
Total Quantity						203.2820 kg		
Total Deducted Quantity						0.0000 kg		
Net Total Quantity						203.28 kg		
Say 203.2820 kg @ (₹) 80.159976 / kg						16295.08		
Unskilled wage						530.57		
Unskilled Person-days						2.03282		
5	79.04.13c -- Providing and laying in foundation, plinth and under floors cement concrete with 40mm nominal siz stone aggregates (metal) i/c ramming in layers and curing complete excluding cost of form work © C.C. 1:4:8 (1 4sand, 8metal)							
SI No	Description	No	L	B	D	CF	Quantity	Remark

pcc work								
1	columns	6	0.900	0.900	0.100	1.0	0.4860	-
2	urinal	1	0.700	0.700	0.100	1.0	0.0490	-
3	floor base	1	7.300	3.500	0.100	1.0	2.5550	-
4	drainage	1	7.300	0.200	0.100	1.0	0.1460	-
5	below drainage wall	1	7.300	0.100	0.100	1.0	0.0730	-

LIST

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0128	Mate	Day	0.0400	435.0	17.4	0.1324	57.58
0125	Mason (for plain stone work) 2nd class	Day	0.0500	435.0	21.75	0.1655	71.97
0126	Mason (for Ornamental stone work) 1st class	Day	0.0500	465.0	23.25	0.1655	76.93
0115	Coolie	Day	1.9000	261.0	495.9	6.2871	1640.93
0002	Hire charges of Concrete Mixer 0.25 to 0.40 cum with Hopper	Day	0.1000	1642.56	164.26	0.3309	543.52
0367	Portland Cement	tonne	0.1700	6627.88	1126.74	0.5625	3728.38
0982	Coarse sand (zone III)	cum	0.4700	448.67	210.87	1.5552	697.79
0295	Stone Aggregate(single size):20 mm nominal size	cum	0.2400	1313.33	315.2	0.7942	1042.99
0293	Stone Aggregate(single size): 40 mm nominal size	cum	0.6500	1149.4	747.11	2.1509	2472.19

Total Quantity					3.3090 cum			
Total Deducted Quantity					0.0000 cum			
Net Total Quantity					3.31 cum			
Say 3.3090 cum @ (₹) 3247.378888 / cum					10745.58			
Unskilled wage					1640.93			
Unskilled Person-days					6.2871			

6	79.04.01 -- Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layer exceeding 20cm in depth consolidating each deposited layers by ramming and watering lead upto 50m and lift upto 1.5m							
---	---	--	--	--	--	--	--	--

SI No	Description	No	L	B	D	CF	Quantity	Remark
-------	-------------	----	---	---	---	----	----------	--------

earth filling								
1	filling available soils	1				3.89	3.8900	-

LIST

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0115	Coolie	Day	0.2360	261.0	61.6	0.9180	239.61
Total Quantity					3.8900 cum		
Total Deducted Quantity					0.0000 cum		
Net Total Quantity					3.89 cum		
Say 3.8900 cum @ (₹) 64.05984 / cum					249.19		
Unskilled wage					239.61		
Unskilled Person-days					0.91804		

7	79.04.02 -- Filling foundation and around masonry work with moorum l/c ramming layers and watering.							
SI No	Description	No	L	B	D	CF	Quantity	Remark
moorum filling								
1	cattle shed	1	7.300	3.500	0.100	1.0	2.5550	-
2	triangular	1	7.300	3.500	0.100	0.5	1.2780	1/2*(3.5*0.1)*7.3
3	ramp	1	7.700	2.000	0.100	0.5	0.7700	1/2*(2*0.1)*7.7

LIST							
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0115	Coolie	Day	0.2360	261.0	61.6	1.0863	283.53
0810	Moorum	cum	1.0000	277.79	277.79	4.6030	1278.67
Total Quantity					4.6030 cum		
Total Deducted Quantity					0.0000 cum		
Net Total Quantity					4.60 cum		
Say 4.6030 cum @ (₹) 352.96144 / cum					1624.68		
Unskilled wage					283.53		
Unskilled Person-days					1.086308		

8	79.06.05j -- Class 25 open bhatta or pajawa burnt brick masonry in plinth and foundation. (j) Cement mortar 1:6 (1cement, 6sand)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
brickwork								
1	long wall	1	7.700	0.200	1.000	1.0	1.5400	-
2	short wall	2	3.500	0.200	0.900	1.0	1.2600	-
3	fodder tank	1	7.300	0.100	0.300	1.0	0.2190	-
4	partition	3	0.400	0.100	0.300	1.0	0.0360	-

5	drain	1	7.800	0.100	0.200	1.0	0.1560	-
6	urinal	2	0.800	0.100	0.600	1.0	0.0960	-
7	urinal	2	0.600	0.100	0.600	1.0	0.0720	-

deduction

8	columns	3	0.200	0.200	1.000	1.0	-0.1200	-
9	side columns	2	0.200	0.200	0.900	1.0	-0.0720	-

LIST

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
MR7240	Brick Class 25 open bhatta or Pajwa burnt (iind class) (Rate at bhatta)	1000 nos	520.0000	3.65	1900.41	1657.2400	6056.62
0115	Coolie	Day	1.8890	261.0	493.03	6.0202	1571.28
0002	Hire charges of Concrete Mixer 0.25 to 0.40 cum with Hopper	Day	0.0105	1642.56	17.25	0.0335	54.97
0367	Portland Cement	tonne	0.0525	6627.88	347.96	0.1673	1108.96
0983	Fine sand (zone IV)	cum	0.2247	431.44	96.94	0.7161	308.96
0124	Mason (brick layer)2nd class	Day	0.3900	435.0	169.65	1.2429	540.67
0123	Mason (brick layer) 1st class	Day	0.3900	465.0	181.35	1.2429	577.96

Total Quantity 3.3790 cum

Total Deducted Quantity -0.1920 cum

Net Total Quantity 3.19 cum

Say 3.1870 cum @ (₹) 3334.860825 / cum 10628.20

Unskilled wage 1571.28

Unskilled Person-days 6.020243

9 **79.06.26** -- Add for Fly Ash brick in item no.0603 and 0605

SI No	Description	No	L	B	D	CF	Quantity	Remark
-------	-------------	----	---	---	---	----	----------	--------

brickwork

1	long wall	1	7.700	0.200	1.000	1.0	1.5400	-
2	short wall	2	3.500	0.200	0.900	1.0	1.2600	-
3	fodder tank	1	7.300	0.100	0.300	1.0	0.2190	-
4	partition	3	0.400	0.100	0.300	1.0	0.0360	-
5	drain	1	7.800	0.100	0.200	1.0	0.1560	-

6	urinal	2	0.800	0.100	0.600	1.0	0.0960	-
7	urinal	2	0.600	0.100	0.600	1.0	0.0720	-
deduction								
8	columns	3	0.200	0.200	1.000	1.0	-0.1200	-
9	side columns	2	0.200	0.200	0.900	1.0	-0.0720	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
7737	Fly ash lime bricks (FALG Bricks) conforming to I.S. 12894	1000 nos	520.0000	3.95	2054.0	1657.2400	6546.1	
MR7240	Brick Class 25 open bhatta or Pajwa burnt (iind class) (Rate at bhatta)	1000 nos	-520.0000	3.65	-1900.41	-1657.2400	-6056.62	
Total Quantity					3.3790 cum			
Total Deducted Quantity					-0.1920 cum			
Net Total Quantity					3.19 cum			
Say 3.1870 cum @ (₹) 159.730688 / cum					509.06			
10	79.04.25c -- Providing and placing in position RCC for roof, beams, columns column footing lintels chhajjas, bal stairs etc, excluding cost of reinforcement & centring but including finishing & curing. © CC 1:2:4 (1cement, 2sa 4graded stone aggregate 20 mm nominal size)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
RCC WORKS								
1	columns	6	0.700	0.700	0.200	1.0	0.5880	-
2	Columns trap section	6	0.0558		0.25/3	1.0	0.0280	(0.25/3)* (0.2*0.2+0.7*0.7)
3	above trap section	6	0.200	0.200	0.350	1.0	0.0840	-
4	above GL	3	0.200	0.200	1.100	1.0	0.1320	back columns
5	above GL	3	0.200	0.200	0.450	1.0	0.0540	front columns=0
6	PLB Long wall	2	7.700	0.200	0.200	1.0	0.6160	-
7	Short wall	2	3.500	0.200	0.200	1.0	0.2800	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR7129	Scaffoldings (L.S.)	sqm	6.8000	11.0	74.8	12.1176	133.29	
0128	Mate	Day	0.0800	435.0	34.8	0.1426	62.01	

0125	Mason (for plain stone work) 2nd class	Day	0.0900	435.0	39.15	0.1604	69.77
0126	Mason (for Ornamental stone work) 1st class	Day	0.0900	465.0	41.85	0.1604	74.58
0115	Coolie	Day	2.3700	261.0	618.57	4.2233	1102.29
0002	Hire charges of Concrete Mixer 0.25 to 0.40 cum with Hopper	Day	0.1000	1642.56	164.26	0.1782	292.7
0367	Portland Cement	tonne	0.3200	6627.88	2120.92	0.5702	3779.48
0982	Coarse sand (zone III)	cum	0.4500	448.67	201.9	0.8019	359.79
0297	Stone Aggregate(single size): 10 mm nominal size	cum	0.2200	972.28	213.9	0.3920	381.17
0295	Stone Aggregate(single size):20 mm nominal size	cum	0.6700	1313.33	879.93	1.1939	1568.04

Total Quantity					1.7820 cum		
Total Deducted Quantity					0.0000 cum		
Net Total Quantity					1.78 cum		
Say 1.7820 cum @ (₹) 4565.685072 / cum					8136.05		
Unskilled wage					1102.29		
Unskilled Person-days					4.22334		

Heading / Description: 2 - coping work							
---	--	--	--	--	--	--	--

1	79.04.13c -- Providing and laying in foundation, plinth and under floors cement concrete with 40mm nominal size stone aggregates (metal) i/c ramming in layers and curing complete excluding cost of form work © C.C. 1:4:8 (14sand, 8metal)						
---	---	--	--	--	--	--	--

SI No	Description	No	L	B	D	CF	Quantity	Remark
coping								
1	long wall	1	7.700	0.200	0.050	1.0	0.0770	-
2	Short wall	2	3.500	0.200	0.050	1.0	0.0700	-
3	ramp	1	7.800	2.100	0.100	1.0	1.6380	-

LIST								
-------------	--	--	--	--	--	--	--	--

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
0128	Mate	Day	0.0400	435.0	17.4	0.0714	31.06
0125	Mason (for plain stone work) 2nd class	Day	0.0500	435.0	21.75	0.0893	38.82
0126	Mason (for Ornamental stone work) 1st class	Day	0.0500	465.0	23.25	0.0893	41.5
0115	Coolie	Day	1.9000	261.0	495.9	3.3915	885.18

0002	Hire charges of Concrete Mixer 0.25 to 0.40 cum with Hopper	Day	0.1000	1642.56	164.26	0.1785	293.2	
0367	Portland Cement	tonne	0.1700	6627.88	1126.74	0.3035	2011.23	
0982	Coarse sand (zone III)	cum	0.4700	448.67	210.87	0.8390	376.41	
0295	Stone Aggregate(single size):20 mm nominal size	cum	0.2400	1313.33	315.2	0.4284	562.63	
0293	Stone Aggregate(single size): 40 mm nominal size	cum	0.6500	1149.4	747.11	1.1603	1333.59	
Total Quantity					1.7850 cum			
Total Deducted Quantity					0.0000 cum			
Net Total Quantity					1.79 cum			
Say 1.7850 cum @ (₹) 3247.378888 / cum					5796.57			
Unskilled wage					885.18			
Unskilled Person-days					3.3914999999999997			
2	79.04.16a -- Add to item No. 04.13 and 04.15 if in place of 40mm metal. (a) If 20mm graded metal is used							
SI No	Description	No	L	B	D	CF	Quantity	Remark
coping								
1	long wall	1	7.700	0.200	0.050	1.0	0.0770	-
2	Short wall	2	3.500	0.200	0.050	1.0	0.0700	-
3	ramp	1	7.800	2.100	0.100	1.0	1.6380	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0293	Stone Aggregate(single size): 40 mm nominal size	cum	-0.5900	1149.4	-678.15	-1.0532	-1210.49	
0295	Stone Aggregate(single size):20 mm nominal size	cum	0.5900	1313.33	774.86	1.0532	1383.13	
Total Quantity					1.7850 cum			
Total Deducted Quantity					0.0000 cum			
Net Total Quantity					1.79 cum			
Say 1.7850 cum @ (₹) 100.587448 / cum					179.55			
Heading / Description: 3 - flooring work								
1	79.12.20b -- Cement concrete flooring 1:2:4 (1cement, 2sand, 4graded stone aggregate, 20mm nominal size) laid in one layer and finished with floating coat of neat cement. (b) 50 mm thick. Cement concrete flooring 1:2:4 (1cement, 2sand, 4graded stone aggregate, 20mm nominal size) laid in one layer and finished with floating coat of neat cement. (b) 50 mm thick.							

SI No	Description	No	L	B	D	CF	Quantity	Remark
flooring work								
1	cattle shed	1	7.300	3.500		1.0	25.5500	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0115	Coolie	Day	0.2430	261.0	63.42	6.2087	1620.46	
0125	Mason (for plain stone work) 2nd class	Day	0.1350	435.0	58.73	3.4493	1500.42	
0367	Portland Cement	tonne	0.0180	6627.88	119.3	0.4599	3048.16	
0982	Coarse sand (zone III)	cum	0.0220	448.67	9.87	0.5621	252.2	
0297	Stone Aggregate(single size): 10 mm nominal size	cum	0.0110	972.28	10.7	0.2811	273.26	
0295	Stone Aggregate(single size):20 mm nominal size	cum	0.0330	1313.33	43.34	0.8432	1107.33	
Total Quantity						25.5500 sqm		
Total Deducted Quantity						0.0000 sqm		
Net Total Quantity						25.55 sqm		
Say 25.5500 sqm @ (₹) 317.569772 / sqm						8113.91		
Unskilled wage						1620.46		
Unskilled Person-days						6.2086500000000004		
Heading / Description: 4 - plastering work								
1	79.10.07d -- 15mm thick cement plaster on rough side of wall in (d) Cement mortar 1:6 (1cement, 6sand)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
plastering work								
1	long wall o/o	1	7.700		1.300	1.0	10.0100	-
2	inner	1	7.300		1.000	1.0	7.3000	-
3	front	1	7.800		0.200	1.0	1.5600	-
4	short wall o/o	2	7.900		1.200	1.0	18.9600	-
5	inner	2	3.500		0.900	1.0	6.3000	-
6	fodder trap	2	7.300		0.300	1.0	4.3800	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0367	Portland Cement	tonne	0.0043	6627.88	28.17	0.2062	1366.45	

0124	Mason (brick layer)2nd class	Day	0.0830	435.0	36.1	4.0263	1751.45
MR7129	Scaffoldings (L.S.)	sqm	0.5351	11.0	5.89	25.9577	285.53
0002	Hire charges of Concrete Mixer 0.25 to 0.40 cum with Hopper	Day	0.0009	1642.56	1.4	0.0412	67.73
0983	Fine sand (zone IV)	cum	0.0182	431.44	7.85	0.8824	380.7
0115	Coolie	Day	0.1963	261.0	51.23	9.5225	2485.38

Total Quantity					48.5100 sqm		
Total Deducted Quantity					0.0000 sqm		
Net Total Quantity					48.51 sqm		
Say 48.5100 sqm @ (₹) 135.863478 / sqm					6590.74		
Unskilled wage					2485.38		
Unskilled Person-days					9.522513		

2	79.13.07 -- White washing with lime on undecorated wall surfaces (3coats) to give an even shade including tho broomed the surface to remove all dirt, dust, mortar drops and other foreign matter.						
---	---	--	--	--	--	--	--

SI No	Description	No	L	B	D	CF	Quantity	Remark
-------	-------------	----	---	---	---	----	----------	--------

plastering work								
1	long wall o/o	1	7.700		1.300	1.0	10.0100	-
2	inner	1	7.300		1.000	1.0	7.3000	-
3	front	1	7.800		0.200	1.0	1.5600	-
4	short wall o/o	2	7.900		1.200	1.0	18.9600	-
5	inner	2	3.500		0.900	1.0	6.3000	-
6	fodder trap	2	7.300		0.300	1.0	4.3800	-

LIST								
------	--	--	--	--	--	--	--	--

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
MR7211	Indigo gum (L.S.)	Packet	0.0933	11.0	1.03	4.5260	49.79
0776	Satna lime	quintal	0.0030	680.71	2.04	0.1455	99.06
0115	Coolie	Day	0.0100	261.0	2.61	0.4851	126.61
0141	White Washer	Day	0.0190	435.0	8.27	0.9217	400.94

Total Quantity					48.5100 sqm		
Total Deducted Quantity					0.0000 sqm		
Net Total Quantity					48.51 sqm		
Say 48.5100 sqm @ (₹) 14.501167 / sqm					703.45		

Unskilled wage						126.61		
Unskilled Person-days						0.4851		
3	79.13.18a -- Snowcem or durocem painting of any shade (a) 2 coats on new work							
SI No	Description	No	L	B	D	CF	Quantity	Remark
plastering work								
1	long wall o/o	1	7.700		1.300	1.0	10.0100	-
2	inner	1	7.300		1.000	1.0	7.3000	-
3	front	1	7.800		0.200	1.0	1.5600	-
4	short wall o/o	2	7.900		1.200	1.0	18.9600	-
5	inner	2	3.500		0.900	1.0	6.3000	-
6	fodder trap	2	7.300		0.300	1.0	4.3800	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR7081	Snowcem or durocem	tonne	0.0002	34294.88	7.2	0.0102	349.37	
0141	White Washer	Day	0.0400	435.0	17.4	1.9404	844.07	
Total Quantity						48.5100 sqm		
Total Deducted Quantity						0.0000 sqm		
Net Total Quantity						48.51 sqm		
Say 48.5100 sqm @ (₹) 25.586002 / sqm						1241.18		
4	79.10.15 -- Extra rate for finishing with a floating cot of neat cement slurry over cement plaster of any thickness							
SI No	Description	No	L	B	D	CF	Quantity	Remark
Neat cement slurry								
1	foder trap	3	2.360	0.400		1.0	2.8320	-
2	-	4	2.360		0.300	1.0	2.8320	-
3	-	4	0.400		0.300	1.0	0.4800	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0124	Mason (brick layer)2nd class	Day	0.0360	435.0	15.66	0.2212	96.22	
0115	Coolie	Day	0.0480	261.0	12.53	0.2949	76.97	
0367	Portland Cement	tonne	0.0020	6627.88	13.26	0.0123	81.44	
Total Quantity						6.1440 sqm		

Total Deducted Quantity							0.0000 sqm	
Net Total Quantity							6.14 sqm	
Say 6.1440 sqm @ (₹) 41.858198 / sqm							257.18	
Unskilled wage							76.97	
Unskilled Person-days							0.294912	
Heading / Description: 5 - Truss work								
1	79.09.03 -- Steel work in built up tubular trusses including cutting, hoisting, fixing in position, welded and bolted special shaped washers etc. complete of Mild steel tubes, electric resistant or induction butt welded							
SI No	Description	No	L	B	D	CF	Quantity	Remark
truss work								
1	75mm dia pole	3	1.200			3.6	12.9600	2 mm thick
2	75mm dia pole	3	2.300			3.6	24.8400	2 mm thick
3	TIE BEAM 50 mm dia	3	3.900			2.37	27.7290	2 mm thick
4	post	3	0.400			2.37	2.8440	2 mm thick
5	strut	6	0.150			2.37	2.1330	2 mm thick
6	150mmx150mmx5mm plate	6	0.883			1.0	5.2980	-
7	Rafter 45 mm dia	6	2.200			2.12	27.9840	2 mm thick
8	purlin 45 mm dia	5	8.100			2.12	85.8600	2 mm thick
9	50 mm dia	1	11.400			2.37	27.0180	2 mm thick
10	GATE	1				35.0	35.0000	2 mm thick
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR7129	Scaffoldings (L.S.)	sqm	0.1489	11.0	1.64	37.4833	412.32	
0115	Coolie	Day	0.0231	261.0	6.03	5.8178	1518.44	
0102	Blacksmith 1st class	Day	0.0105	465.0	4.89	2.6444	1229.66	
MR7161	M.S. tubes, electric resistant or induction butt welded	kg	1.0718	110.0	117.9	269.7328	29670.61	
Total Quantity						251.6660 kg		
Total Deducted Quantity						0.0000 kg		
Net Total Quantity						251.67 kg		
Say 251.6660 kg @ (₹) 135.672948 / kg						34144.27		
Unskilled wage						1518.44		

Unskilled Person-days						5.81776677895019		
2	79.PWD.10.16.1 -- providing and fixing precast galvanized steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness (TCT), zinc coating 120 gms as per IS:277 In 240mpa steel grade, 5-7 microns epoxy primer on both the sides of sheet and polyester top coat 15-18 microns using self drilling / self tapping screws or with polymer coated J or L hooks ,bolts and nuts and or G.I. seam bolts and nuts , G.I. plain and bitumen washers complete. providing and fixing precast galvanized steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness zinc coating 120 gms as per IS:277 In 240mpa steel grade, 5-7 microns epoxy primer on both the sides of sheet polyester top coat 15-18 microns using self drilling / self tapping screws or with polymer coated J or L hooks ,bolts and nuts and or G.I. seam bolts and nuts , G.I. plain and bitumen washers complete. (1) Ridges plain (500-600mm)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
ridge plain								
1	ridge plain	1	8.100			1.0	8.1000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR7218	sundries/ overhead charges (L.S.)	each	1.4574	11.7	17.05	11.8051	138.12	
0115	Coolie	Day	0.0812	261.0	21.19	0.6576	171.64	
0156	Carpenter (average)	Day	0.0272	435.0	11.84	0.2205	95.94	
0130	Mistry	Day	0.0203	465.0	9.44	0.1644	76.45	
MR7256	precast galvanized steel plain ridges	meter	1.1441	460.0	526.27	9.2669	4262.77	
Total Quantity						8.1000 meter		
Total Deducted Quantity						0.0000 meter		
Net Total Quantity						8.10 meter		
Say 8.1000 meter @ (₹) 591.6494 / meter						4792.36		
Unskilled wage						171.64		
Unskilled Person-days						0.6576237620689654		
3	79.PWD.10.11 -- supply and fixing of precast galvanized iron profile sheets (size,shape and pitch of corrugated sheet approved by Engineer-in-charge)0.50mm +/- total coated thickness (TCT),zinc coating 120 gms as per IS:277 In 240mpa steel grade,5-7 microns epoxy primer on both the side of sheet and polyester top coat 15-18 microns.sheet shall have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 meters or as desired by Engineer-in-charge. the sheet shall be fixed using self drilling/ self tapping screws of size (5.5x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8 mm diameter and bitumen and G.I. Limpet washers or with G.I. Limpet washers filled with white lead complete upto any pitch in horizontal or vertical or curved surfaces excluding the cost of purlins ,rafters and trusses and including cutting to size and shape wherever required.							
SI No	Description	No	L	B	D	CF	Quantity	Remark
profile sheet								
1	profile sheet	2	8.100	2.440		1.0	39.5280	-
LIST								

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
1209	G.I. Plain washer thick	100 nos	2.2023	4.76	10.48	87.0516	414.37
1208	Bitumen washer	100 nos	2.2023	2.5	5.51	87.0516	217.63
MR7218	sundries/ overhead charges (L.S.)	each	1.6730	11.7	19.57	66.1299	773.72
0115	Coolie	Day	0.0432	261.0	11.28	1.7081	445.82
0156	Carpenter (average)	Day	0.0432	435.0	18.8	1.7081	743.03
0130	Mistry	Day	0.0108	465.0	5.03	0.4279	198.99
1023	Galvanised steel J or L hooks 8 mm dia	10 nos	2.2023	17.93	39.49	87.0516	1560.83
MR7255	Precoated galavanised iron profile sheet 0.50mm TCT	sqm	1.0810	560.0	605.37	42.7303	23928.94

Total Quantity					39.5280 sqm		
Total Deducted Quantity					0.0000 sqm		
Net Total Quantity					39.53 sqm		
Say 39.5280 sqm @ (₹) 722.681776 / sqm					28566.17		
Unskilled wage					445.82		
Unskilled Person-days					1.7081128626206896		

4	79.13.35a -- Painting with enamel paint, brushing, interior to give an even shade I/n cleaning the surface of all c and other foreign matter on steel and other metal surfaces. (a) 3 coats						
---	--	--	--	--	--	--	--

SI No	Description	No	L	B	D	CF	Quantity	Remark
iron painting								
1	IRON PAINTING	1				18.5	18.5000	-

LIST								
-------------	--	--	--	--	--	--	--	--

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
MR7213	Brushes (L.S.)	each	0.5970	11.2	6.69	11.0445	123.7
0115	Coolie	Day	0.0840	261.0	21.92	1.5540	405.59
0131	Painter	Day	0.0840	465.0	39.06	1.5540	722.61
8507	Textured exterior paint	Litre	0.2400	350.02	84.0	4.4400	1554.09

Total Quantity					18.5000 sqm		
Total Deducted Quantity					0.0000 sqm		
Net Total Quantity					18.50 sqm		
Say 18.5000 sqm @ (₹) 157.742208 / sqm					2918.23		

Unskilled wage			405.59		
Unskilled Person-days			1.554		
6	Lump sum Type : Material	Miscellaneous /Contingencies charges	2%		2919.0
7	Lump sum Type : Material	BFT/TA/Mate	1%		1459.0
8	Lump sum Type : Material	Display Board / CIB			3000.0
Total (₹) :					154868.26
Rounded Total (₹) :					1,54,868.00
Rupees One Lakh Fifty Four Thousand Eight Hundred and Sixty Eight Only					
Unskilled Manpower wages					14707.67
Materials (Includes Extra Charges)					121372.10
Carriage					0.00
Skilled					3943.95
SemiSkilled					7466.54
Lumpsum Admin					0.00
Lumpsum Material					7378.00
No of Person days					56.35

Structural Drawing

